

Cooling for General Hospital

Project

A customer's 70kW chiller broke down due to evaporator failure for which the repair was estimated to take approximately eight weeks. The customer called Cool Energy as air conditioning for their Oncology department was affected by the breakdown. This area has specialist scanners for high level patient care and therefore cooling was of paramount importance to our customer who needed supply urgently.



Cool Energy Solution

The Cool Energy rental engineer liaised with the customer and visited site to ensure that the correct connections, sufficient space and power was available.

The customer agreed to isolate their damaged chiller and utilize its powers and water connections for the rental chiller in order to resolve the situation quickly and safely.

Cool Energy delivered the chiller along with 2 engineers who installed the chiller by connecting 2" hose into customer's process within 24 hours of receiving order confirmation.



Equipment Supplied

A 70kW chiller with integral pump and tank set complete with 12m x 2" flexible water hose and 2" connections were supplied on 30ft HIAB transport.



Call us free on 0800 169 3861 for an emergency visit or to order equipment fast.